

SafetyWhips.com

Mining & Industrial Safety Equipment

USA

TEL: 602.424.2520 • FAX: 602.424.9777 • Email: sales@safetywhips.com

CANADA

TEL: 604.560.5080 • FAX: 604.560.5090 • Email: lugo@safetywhips.com



Catalog Index

Page 1	Index	Page 13:	Super Duty Fiberglass Whips Heavy Duty LED Whips
Page 2:	About SafetyWhips	Page 14:	Metal Whips, Powered Light Duty ATV Whips Light Duty Whips
Page 3:	Wheel Chocks	Page 15:	Telescoping Whips
Page 4:	Wheel Chocks	Pages 16	Hitch Mounts
Page 5:	Vehicle and Equipment ID Panels LED Programmable Numeric, Character	Pages 17	Whip Mount Bases
Page 6:	Vehicle and Equipment ID Panels LED Programmable Numeric, Character Arrow / Message Panels w/ Remote Control	Pages 18	Whip Mounts: Permanent & Temporary
Page 7:	Vehicle ID Panels, Reflective-LED Backlit	Pages 19	Universal Platform Mount
Page 8:	Signal / Status Lights VID Accessories 3 Sided VID Displays	Pages 20	Safety Whip Flags
Page 9	Heavy Duty Fiberglass Whips, Threaded / Non-powered	Pages 21	LED Light Heads for Whips
Page 10:	Heavy Duty Fiberglass Whips, Threaded / Powered	Pages 22	Battery Powered Lights Automotive Lamp Shields
Page 11:	Heavy Duty Fiberglass Whips, Quick Disconnect / Non-powered	Pages 23	Warning Lights
Page 12:	Heavy Duty Fiberglass Whips, Quick Disconnect / Powered	Pages 24	Accessories
		Pages 25	Aviation / Transportation
		Pages 26	Transportation, Personal Protection

SafetyWhips USA

2115 W. Mountain View Rd., Phoenix, AZ 85021
Tel. 602-424-2500 Fax: 602-424-9777
Sales@SafetyWhips.com
www.SafetyWhips.com

SW SafetyWhips Canada,

677 - 192 St.#107 Surrey, BC V3S 3X1
Tel. 604-560-5080 Fax: 604-560-5090
SalesCanada@SafetyWhips.com
www.SafetyWhips.ca



About SafetyWhips

SafetyWhips USA is a quality manufacturer of market-driven safety products for the mining & commercial industries.

- Privately owned company located in Phoenix, Arizona.
- Founded in May 2004.
- A leading safety and warning whips manufacturer.
- SafetyWhips turns ideas into successful brands with innovative, market-leading safety products.
- Independent and local ownership provides focus and flexibility needed to achieve success.



Our Mission

Our mission is to be the preferred and most trusted resource for safety products by exceeding customers' expectations and achieving market leadership.

Our Vision

We want to earn our customers' loyalty as a Leader committed to never ending improvement in Quality, Productivity, Customer Service, Safety and Environmental Impact.



Wheel Chocks · General Purpose, Polyurethane




WC-UO1400: Single

WC-UO1400-2: Set of 2
WC-UO1400-2R: 2 roped

WC-UO1400			
LOAD CAPACITY (1 each)	TIRE DIAMETER	DIMENSIONS	WEIGHT
5 tons (US)	27-35 in	8.25 L • 7 W • 6 H in	2.5 lb
4,536 kg	686-889 mm	20.96 L • 17.78 W • 15.24 H cm	1.134 kg



WC-UO1500: Single

WC-UO1500-2: Set of 2
WC-UO1500-2R: 2 roped

WC-UO1500			
LOAD CAPACITY (1 each)	TIRE DIAMETER	DIMENSIONS	WEIGHT
20 tons (US)	27-35 in	11 L • 8 W • 8 H in	3.7 lb
18,144 kg	686-889 mm	22.94 L • 20.32 W • 20.32 H cm	1.678 kg

Wheel Chocks · General Purpose, Rubber



WC-1100BY-R2: 2 roped

WC-1100BY-R2	
DIMENSIONS	WEIGHT
4 L • 8 W • 4 H in	7.5 lb
10.16 L • 20.32 W • 10.16 H cm	3.40 kg



WC-RB1200: Single

WC-RB1200-2: Set of 2
WC-RB1200-2R: 2 roped

WC-RB1200			
LOAD CAPACITY (1 each)	TIRE DIAMETER	DIMENSIONS	WEIGHT
6 tons (US)	32 in	8.5 L • 7.5 W • 6.25 H in	7 lb
5,443 kg	812.8 mm	21.59 L • 19.05 W • 16.51 H cm	3.18 kg



WC-RB1010: Single

WC-RB1010-2: Set of 2
WC-RB1010-2R: 2 roped

WC-RB1010			
LOAD CAPACITY (1 each)	TIRE DIAMETER	DIMENSIONS	WEIGHT
13 tons (US)	32 in	7.5 L • 9.5 W • 5.75 H in	7.4 lb
11,793 kg	812.8 mm	19.05 L • 24.13 W • 14.61 H cm	3.36 kg



WC-RB1020: Single

WC-RB1020: Set of 2
WC-RB1020-2R: 2 roped

WC-RB1020			
LOAD CAPACITY (1 each)	TIRE DIAMETER	DIMENSIONS	WEIGHT
13 tons (US)	40-44 in	10 L • 8 W • 8.5 H in	8.5 lb
11,793 kg	1016-1117.6 mm	25.4 L • 20.32 W • 21.59 H cm	3.86 kg

Wheel Chocks · Large Equipment, Polyurethane




WC-UY2200: Single

WC-UY2200			
LOAD CAPACITY (1 each)	TIRE DIAMETER	DIMENSIONS	WEIGHT
35 tons (US)	36-46 in	21 L • 11 W • 12 H in	22 lb
31,751kg	914-1168 mm	53.34 L • 27.94 W • 30.48 H cm	9.979 kg




WC-UY2400 Single

WC-UY2400			
LOAD CAPACITY (1 each)	TIRE DIAMETER	DIMENSIONS	WEIGHT
100 tons (US)	65-95 in	17.5 L • 14.5 W • 14.5 H in	20 lb
90,718 kg	1651-2413 mm	44.45 L • 36.83 W • 36.83 H cm	9.072 kg



WC-UY2700: Single

WC-UY2700			
LOAD CAPACITY (1 each)	TIRE DIAMETER	DIMENSIONS	WEIGHT
50 tons (US)	40 in	10.5 L • 15 W • 12 H in	18.2 lb
45,359 kg	1016 mm	26.67 L • 38.10 W • 30.48 H cm	8.225 kg



WC-UY3800: Single

WC-UY3800			
LOAD CAPACITY (1 each)	TIRE DIAMETER	DIMENSIONS	WEIGHT
255 tons (US)	95-142 in	21.9 L • 14.9 W • 10.6 H in	39 lb
231,332 kg	2413-3607 mm	55.63 L • 37.85 W • 26.92 H cm	17.69g

CAUTION
WHEELS MUST BE CHOCKED
BEFORE LOADING AND UNLOADING

Safety Signage –
 Wheels must be chocked
 • Used for chocking regulations compliance
 • 11" x 15"
 • Available on steel or adhesive vinyl

Vehicle & Heavy Equipment, ID Panels, Programmable & RS232 Compatible

Visible up to 2000 feet

Maintenance Free – Most Dependable in the Industry
 Positively identify vehicles on the job-site
 Bright and Rugged LED Displays.
 VID's beam through dusty air and weather.
 Field Tested for Over 10 Years



RS232
 Communications
 Options



Conveniently change the digits (1 to 9) or *characters (including all letters A - Z), using magnetic switches. They stay set until changed again with the magnet.
 *on character models only

- Designed for 24 hour use: the Vehicle ID Display is programmed for brighter illumination in the daytime and a sensor dims the LED output for nighttime use.
- Character VID's can be programmed for all numeric and all 26 alpha characters.
- Once programmed, the numbers or letters use *Locking* technology and do not need reprogramming upon shut down and startup.
- SafetyWhips has built-in *Secure Protection* technology. This insures safe-site operation by preventing VID's from displaying incorrect characters
- Light weight and Easy to mount - VID's can be installed by one technician
- Tough and dependable, SafetyWhips VID's come with a 5 year warranty
- Super-sealed internally as well as externally. SafetyWhips VID's are protected from dirt moisture, high-pressure washing, and vibration. External damage to your VID will not affect its continued operation.
- Available in red, amber, green, blue LEDs.
- Custom color frames available



Truck ID in use


IP Rated
 IP66
 IP67




VID-5C12-A

12 inch Numeric Displays, Programmable 0 to 9

Numeric Display 12" Character Size, Visible up to 500 ft., 24V										
Part Number	LED Color	2 to 4 Numeric Characters, LED, Programmable					12 Volt available upon request			
		Digits	Character Height	Weight	Frame Height	Frame Width	Volts	Amps	Watts	
VID-2N12L-R	Red	2	304 mm 12 in	7 kg 15.5 lbs	438.15 mm 17.25 in	498.10 mm 19.61 in	24	0.33	8	
VID-2N12L-A	Amber									
VID-2N12L-G	Green									
VID-2N12L-B	Blue									
VID-3N12L-R	Red	3	304 mm 12 in	9.3 kg 20.5 lbs	438.15 mm 17.25 in	710.95 mm 27.99 in	24	0.49	12	
VID-3N12L-A	Amber									
VID-3N12L-G	Green									
VID-3N12L-B	Blue									
VID-4N12L-R	Red	4	304 mm 12 in	11.2 kg 24.8 lbs	438.15 mm 17.25 in	924.05 mm 36.38 in	24	0.66	16	
VID-4N12L-A	Amber									
VID-4N12L-G	Green									
VID-4N12L-B	Blue									
Accessories:	Mounting Brackets VID-S10-2	Power Extension Cord VID-PC-EXT-50-1	Power Cord Splitter 2 VID's VID-PC-EXT12-2Y	Power Cord Splitter 3 VID's VID-PC-EXT12-3Y						



VID-2N12L-R



VID-3N12L-A



VID-3C12-B

12 inch Character Displays, Programmable A to Z and 0 to 9

Character Display 12" Character Size, Visible up to 500 ft., 24V										
Part Number	LED Color	2 to 4 Numeric Characters, LED, Programmable					12 Volt available upon request			
		Characters	Character Height	Weight	Frame Height	Frame Width	Volts	Amps	Watts	
VID-2C12-R	Red	2	304 mm 12 in	10.4 kg 23 lbs	438.15 mm 17.25 in	622.05 mm 24.49 in	24	1.0	24	
VID-2C12-A	Amber									
VID-2C12-G	Green									
VID-2C12-B	Blue									
VID-3C12-R	Red	3	304 mm 12 in	11.6 kg 25.5 lbs	438.15 mm 17.25 in	899.16 mm 35.40 in	24	1.5	36	
VID-3C12-A	Amber									
VID-3C12-G	Green									
VID-3C12-B	Blue									
VID-4C12-R	Red	4	304 mm 12 in	14.1 kg 31 lbs	438.15 mm 17.25 in	1171.95 mm 46.14 in	24	2.0	48	
VID-4C12-A	Amber									
VID-4C12-G	Green									
VID-4C12-B	Blue									
VID-5C12-R	Red	5	304 mm 12 in	18.59 kg 41 lbs	438.15 mm 17.25 in	1443.99 mm 56.58 in	24	2.5	60	
VID-5C12-A	Amber									
VID-5C12-G	Green									
VID-5C12-B	Blue									
Accessories:	Mounting Brackets VID-S10-2	Power Extension Cord VID-PC-EXT-50-1	Power Cord Splitter 2 VID's VID-PC-EXT12-2Y	Power Cord Splitter 3 VID's VID-PC-EXT12-3Y						

18 inch Character Displays, Programmable A to Z and 0 to 9

Character Display 18" Character Size, Visible up to 1,000 ft., 24V
 1 Character, LED, Programmable 12 Volt available upon request

Part Number	LED Color	Character	Character Height	Weight	Frame Height	Frame Width	Volts	Amps	Watts
VID-1C18-R	Red	1	457.2 mm 18 in	7.3 kg 16 lbs	575.31 mm 22.65 in	438.15 mm 17.25 in	24	1.0	24
VID-1C18-A	Amber								
VID-1C18-G	Green								
VID-1C18-B	Blue								

Accessories: Mounting Brackets VID-S18-2 | Power Extension Cord VID-PC-EXT-50-1 | Power Cord Splitter 2 VID's VID-PC-EXT18/24-2Y | Power Cord Splitter 3 VID's VID-PC-EXT18/24-3Y



24 inch Character Displays, Programmable A to Z and 0 to 9

Character Display 18" Character Size, Visible up to 1,000 ft., 24V
 1 Character, LED, Programmable 12 Volt available upon request

Part Number	LED Color	Character	Character Height	Weight	Frame Height	Frame Width	Volts	Amps	Watts
VID-1C24-R	Red	1	609.6 mm 24 in	9.5 kg 21 lbs	803.91 mm 31.65 in	438.15 mm 17.25 in	24	1.5	36
VID-1C24-A	Amber								
VID-1C24-G	Green								
VID-1C24-B	Blue								

Accessories: Mounting Brackets VID-S24-2 | Power Extension Cord VID-PC-EXT-50-1 | Power Cord Splitter 2 VID's VID-PC-EXT18/24-2Y | Power Cord Splitter 3 VID's VID-PC-EXT18/24-3Y



36 inch Numeric Displays, Programmable 0 to 9*

Numeric Display 36" Character Size, Visible up to 2,000 ft., 24V
 1 Digit Numeric, LED, Programmable 12 Volt available upon request


Part Number	LED Color	Digit	Character Height	Weight	Frame Height	Frame Width	Volts	Amps	Watts
VID-1N36-R	Red	1	914.4 mm 36 in	12.2 kg 27 lbs	1032.51 mm 40.56 in	438.15 mm 17.25 in	24	2.5	60
VID-1N36-A	Amber								
VID-1N36-G	Green								
VID-1N36-B	Blue								

Accessories: Mounting Brackets VID-S36-2 | Power Extension Cord VID-PC-EXT-50-1 | Power Cord Splitter 2 VID's VID-PC-EXT36-2Y | Power Cord Splitter 3 VID's VID-PC-EXT36-3Y



Vehicle ID programmable & dynamic w/communication capability

Arrow Board / Message Board



VID-3C12-MBC-24v
 3 Characters
 17.25 x 38 inches
 12V-24V
 Power rating 57W
 28 lbs

Multi-purpose board can be mounted anywhere that directional arrow indicators are required. Additionally, this unit is an integral part of a messaging system on heavy equipment or on stationary structures. The Message Board utilizes the same dependable technology of SafetyWhips' Vehicle ID Displays.

This board can be pre-programmed to display your selected messages regarding Equipment Status, Truck Requires Maintenance, is Down, Not in Service. Also allowing Alternating Use of Arrows for Traffic Guidance along with messages.



RS232
 Communications
 Options

3-Sided Vehicle Identification Display

1 VID Per Side With Frame
 VID-3S-BL3N12

Day and Night visible LED Identification Display

Rugged and Real-World Tested

Heavy gauge 1/8" Steel. It's light weight and easy to install. With impact resistance & withstands power hose cleaning. This model is built to withstand extreme vibration. It's black powder coated finish handles maximum environmental protection.

Universal Design Fits:

- 2 Digit VID programmable
- 2 digit VID backlit
- 3 digit VID programmable
- 3 digit VID backlit

Made in the USA

Beacon Light and Whip Available Upon Request



Backlit Vehicle ID Panels, Permanent Text

These Panels are Heavy Duty and Weather Sealed, just like our programmable units. The backlit characters are Reflective and Translucent, for day or night visibility, even when not under power. Available in black or amber

Available in
120-240/277
VAC

IP Rated

IP66

IP67

Backlit Character Display 18" Character Size, Visible up to 1,000 ft., 24V								
1 Character, Backlit LED								
12 Volt available upon request								
Part Number	Character	Character Height	Weight	Frame Height	Frame Width	Volts	Amps	Watts
VID-BL1C18-BK	1	457.2 mm 18 in	6.57 kg 14.5 lbs	575.31 mm 22.65 in	438.15 mm 17.25 in	24	2.08	50
Accessories:	Mounting Brackets VID-S18-2	Power Extension Cord VID-PC-EXT-50-1	Power Cord Splitter 2 VID's VID-PC-EXT18/24-2Y	Power Cord Splitter 3 VID's VID-PC-EXT18/24-3Y				


Backlit Character Display 24" Character Size, Visible up to 1,500 ft., 24V								
1 Character, Backlit LED								
12 Volt available upon request								
Part Number	Character	Character Height	Weight	Frame Height	Frame Width	Volts	Amps	Watts
VID-BL1C24-BK	1	609.6 mm 24 in	8.84 kg 19.5 lbs	803.91 mm 31.65 in	438.15 mm 17.25 in	24	3.33	80
Accessories:	Mounting Brackets VID-S24-2	Power Extension Cord VID-PC-EXT-50-1	Power Cord Splitter 2 VID's VID-PC-EXT18/24-2Y	Power Cord Splitter 3 VID's VID-PC-EXT18/24-3Y				

Backlit Character Display 36" Character Size, Visible up to 2,000 ft., 24V								
1 Character, Backlit LED								
12 Volt available upon request								
Part Number	Digit	Character Height	Weight	Frame Height	Frame Width	Volts	Amps	Watts
VID-BL1C36-BK	1	914.4 mm 36 in	12.7 kg 28 lbs	1032.51 mm 40.56 in	438.15 mm 17.25 in	24	4.17	100
Accessories:	Mounting Brackets VID-S36-2	Power Extension Cord VID-PC-EXT-50-1	Power Cord Splitter 2 VID's VID-PC-EXT36-2Y	Power Cord Splitter 3 VID's VID-PC-EXT36-3Y				

Backlit Character Display 12" Character Size, Visible up to 500 ft., 24V								
2 to 4 Characters, Backlit LED								
12 Volt available upon request								
Part Number	Characters	Character Height	Weight	Frame Height	Frame Width	Volts	Amps	Watts
VID-BL2C12-BK	2	304 mm 12 in	9.98 kg 22 lbs	438.15 mm 17.25 in	621.03 mm 24.45 in	24	2.5	60
VID-BL3C12-BK	3	304 mm 12 in	11.34 kg 25 lbs	438.15 mm 17.25 in	895.35 mm 35.25 in	24	3.75	90
VID-BL4C12-BK	4	304 mm 12 in	12.70 kg 28 lbs	438.15 mm 17.25 in	1,169.67 mm 46.05 in	24	5.0	120
Accessories:	Mounting Brackets VID-S10-2	Power Extension Cord VID-PC-EXT-50-1	Power Cord Splitter 2 VID's VID-PC-EXT12-2Y	Power Cord Splitter 3 VID's VID-PC-EXT12-3Y				



No Peeling Tape or Broken Numbers!



VID-BL1C36



VID-BL3C12

Also Available,

as an Economical, Reflective, but non-lit, VID Panel; in the same type of sealed frame as our standard panels.

VID Accessories

VID Brackets, Pre-Drilled

- Mount to any SafetyWhips VID sign
- Hardware available upon request
- Made of powder coated steel

For 12 inch displays: VID-S10-2
For 18 inch displays: VID-S18-2
For 24 inch displays: VID-S24-2
For 36 inch displays: VID-S36-2



PC-EXT-50-1:
50 foot power cord,
two wire and Deutsch connector

PC-EXT-50-2:
50 foot power cord,
Deutsch connector both ends

Signal Lights

These simple, yet versatile signals are in-cab controlled to show equipment or operation status. Weather Resistant.

Uses Include:

- Stopped VS Running Status
- Autonomous Operation VS Manned Operation Status
- Ready to Load VS Stop/Do Not Enter

Available as:

- Single or double units
- When in use, panels flash either blue or red or color of choice
- Other colors available.
- Single controller for one or two units.



VID-BL2SIG6-24V-R/B
Red & Blue signal light shown above

24V Standard , 12V available upon request
14.5 Watts, 0.6 Amps
15 lbs
11 x 35 3/8 inches

available in
120-240/277
VAC



IP Rated
IP66
IP67

Characters	Character Height	Weight	Frame Height	Frame Width	Volts	Amps	Wat
5	304 mm 12 in	18.59 kg 41 lbs	438.15 mm 17.25 in	1443.99 mm 56.58 in	24	2.5	60

VID-5C12-A

Shown with Signal Light VID-BL2SIG6-24V-R/G

3-Sided VID Displays



VID-LA4NP-SX
3 or 4 Characters
LED Backlit w/Reflective sign panels
3 Magnet-mount feet
order with or without strobes
Body Dimensions:
28" x 28" x 28W 17" H
12-24 V
11 lbs



VID-3PR-KIT-1
3 Sided Display Kit for One Side Plastic Casing
Flourescent Lime Green Reflective Vinyl
-> Includes black cut vinyl bordering
-> Polycarbonate size: 11"H x 23"L
-> 9.25"h lettering, black cut vinyl
NUMBER: "insert desired numbers/letters here"

PART NUMBERS:
VID-3PR-KIT-2
VID-3PR-KIT-3

Available without whip or beacon



VID-SA4FA-SX
Lite Duty for:
Pick-up or Passenger Vehicle
12VDC standard
24V available upon request
20" x 20" x 20W 10" H
6 lbs



New Item!




New Item!

Hitch & Toolbox Mounts:
VID Display and Flag bolt onto 1/4" Steel Platform.
Ideal for Ford aluminum body trucks (non-magnetic),
and an additional mount option for all trucks.
See page 19 for details.

Non-powered Heavy Duty Fiberglass Whips, Threaded Mount

Whip Height	Single Piece Threaded Whips			Two Piece Threaded Breakdown Whips		
	Whip 11.5x11.5 Mesh Flag	Whip 11.5x11.5 "X" Flag	Whip 16x16 "X" Flag	Whip 11.5x11.5 Mesh Flag	Whip 11.5x11.5 "X" Flag	Whip 16x16 "X" Flag
5ft	W05NP-M	W05NP-SXY	W05NP-XY	W05BDSTNP-M	W05BDSTNP-SXY	W05BDSTNP-XY
8ft	W08NP-M	W08NP-SXY	W08NP-XY	W08BDSTNP-M	W08BDSTNP-SXY	W08BDSTNP-XY
10ft	W10NP-M	W10NP-SXY	W10NP-XY	W10BDSTNP-M	W10BDSTNP-SXY	W10BDSTNP-XY
12ft	W12NP-M	W12NP-SXY	W12NP-XY	W12BDSTNP-M	W12BDSTNP-SXY	W12BDSTNP-XY



W05NP-XY



W08BDSTNP-XY
Breakdown whip shown above.



Whip Extensions Fiberglass Threaded Mount Non-powered

Custom lengths available

Size	Part Numbers
1 ft	EXT-1NP
2 ft	EXT-2NP
3 ft	EXT-3NP
4 ft	EXT-4NP
6 ft	EXT-6NP

Standard Flags



FLAG11-O:
11.5 x 11.5 inch
Orange (PMS 171 C)
Mesh flag



FLAG11-O-XY:
11.5 x 11.5 inch
Yellow (PMS Yellow C)
Mesh flag with reflective yellow X



FLAG16-O-XY:
16x16 inch
Orange (PMS 171 C)
Mesh flag with reflective yellow X

For other flag options, refer to page 20
Custom sizes available upon request.



Safety X available in White (W) or Yellow (Y)
For 11.5 x 11.5 or 16x16 inch

Whip Mounts

Non-powered, for Threaded Mount

Steel Thread Mount



Non-Powered Thread mount
Optional

519.343NP

Heavy Duty Spring Mounts



Heavy Duty Spring Mount
Highly recommended to help reduce whip breakage.
Non-Powered

a : 519.309NP Stainless Steel
b : 519.30BNP Zinc Plated Steel

Angle Bracket Mounts (ABM)



ABM: Angle Bracket Mount
Attach whips to toolbox, rack or truck bed with this heavy duty bracket.

Hitch Mount



HM1NPA :Hitch Mount with Non-Powered Threaded Mount and 107 dB Backup Alarm

For other mount options see to pages 16 to 19

Powered Heavy Duty Fiberglass Whips, Threaded Mount

Whip Height	Single Piece Threaded Whips			Two Piece Threaded Breakdown Whips		
	Whip 11.5x11.5 Mesh Flag	Whip 11.5x11.5 "X" Flag	Whip 16x16 "X" Flag	Whip 11.5x11.5 Mesh Flag	Whip 11.5x11.5 "X" Flag	Whip 16x16 "X" Flag
5ft	W05-M	W05-SXY	W05-XY	W05BDST-M	W05BDST-SXY	W05BDST-XY
8ft	W08-M	W08-SXY	W08-XY	W08BDST-M	W08BDST-SXY	W08BDST-XY
10ft	W10-M	W10-SXY	W10-XY	W10BDST-M	W10BDST-SXY	W10BDST-XY
12ft	W12-M	W12-SXY	W12-XY	W12BDST-M	W12BDST-SXY	W12BDST-XY



W05-XY with AL8CA



W08BDST-XY Breakdown whip shown above with optional LED whip light



Whip Extensions Fiberglass Threaded Mount Powered Custom lengths available

Size	Part Numbers
1 ft	EXT-1
2 ft	EXT-2
3 ft	EXT-3
4 ft	EXT-4
6 ft	EXT-6

Standard Flags



FLAG11-O:
11.5 x 11.5 inch
Orange (PMS 171 C)
Mesh flag



FLAG11-O-XY:
11.5 x 11.5 inch
Yellow (PMS Yellow C)
Mesh flag with reflective yellow X



FLAG16-O-XY:
16x16 inch
Orange (PMS 171 C)
Mesh flag with reflective yellow X

For other flag options, refer to page 20
Custom sizes available upon request.

Common LED Whip Lights

Product Number					
Flashing	AL8FR	AL8FA	AL8FB	AL8FW	AL8FG
Constant	AL8CR	AL8CA	AL8CB	AL8CW	AL8CG

other flight options available
refer to page 21

Whip Mounts

Powered, for Threaded Mount

Steel Thread Mounts



Powered Thread mounts
Optional
a : 519.343.RCA
b : 519.343

Heavy Duty Spring Mounts



Heavy Duty Spring Mount
Highly recommended to help reduce whip breakage.

c : 519.309 Stainless Steel
d : 519.30B Zinc Plated Steel

Angle Bracket Mounts (ABM)



ABM: Angle Bracket Mount
Attach whips to toolbox, rack or truck bed with this heavy duty bracket.

Hitch Mount



HM1A : Hitch Mount
with Standard Threaded Mount and 107 dB Backup Alarm

For other mount options see to pages 16 to 19

Non-powered Heavy Duty Fiberglass Whips, Quick Disconnect

Whip Height	Single Piece Quick Disconnect Whips			Two Piece Quick Disconnect Breakdown Whips		
	Whip 11.5x11.5 Mesh Flag	Whip 11.5x11.5 "X" Flag	Whip 16x16 "X" Flag	Whip 11.5x11.5 Mesh Flag	Whip 11.5x11.5 "X" Flag	Whip 16x16 "X" Flag
5ft	SW05QDNP-M	SW05QDNP-SXY	SW05QDNP-XY	SW05QDNP2-M	SW05QDNP2-SXY	SW05QDNP2-XY
8ft	SW08QDNP-M	SW08QDNP-SXY	SW08QDNP-XY	SW08QDNP2-M	SW08QDNP2-SXY	SW08QDNP2-XY
10ft	SW10QDNP-M	SW10QDNP-SXY	SW10QDNP-XY	SW10QDNP2-M	SW10QDNP2-SXY	SW10QDNP2-XY
12ft	SW12QDNP-M	SW12QDNP-SXY	SW12QDNP-XY	SW12QDNP2-M	SW12QDNP2-SXY	SW12QDNP2-XY



SW05QDNP-XY



SW08QDNP2-XY
Breakdown whip shown above.



Whip Extensions Fiberglass
QD Mount Non-powered
Custom lengths available

Size	Part Numbers
1 ft	EXT-1QDNP
2 ft	EXT-2QDNP
3 ft	EXT-3QDNP
4 ft	EXT-4QDNP
6 ft	EXT-6QDNP

Standard Flags



FLAG11-O:
11.5 x 11.5 inch
Orange (PMS 171 C)
Mesh flag



FLAG11-O-XY:
11.5 x 11.5 inch
Yellow (PMS Yellow C)
Mesh flag with reflective yellow X



FLAG16-O-XY:
16x16 inch
Orange (PMS 171 C)
Mesh flag with reflective yellow X

For other flag options, refer to page 20
Custom sizes available upon request.



Safety X available in
White (W) or Yellow (Y)
For 11.5 x 11.5 or 16x16 inch

Whip Mounts

Non-powered, for Quick Disconnect Mount

Steel QD Mounts



Stainless Steel QD Mount
For quick disconnect whips,

SWQDNP: Non Powered

Heavy Duty Spring Mounts



Heavy Duty Spring Mount
Highly recommended to help reduce whip breakage.
Non-Powered

a : 519.309NP Stainless Steel
b : 519.30BNP Zinc Plated Steel

Angle Bracket Mounts (ABM)



ABM: Angle Bracket Mount
Attach whips to toolbox, rack or truck bed with this heavy duty bracket.

Hitch Mount



HMQDNP A : Hitch Mount with Non-Powered Quick-Connect Mount and 107 dB Backup Alarm


For other mount options see to pages 16 to 19

Powered Heavy Duty Fiberglass Whips, Quick Disconnect

Whip Height	Single Piece Quick Disconnect Whips			Two Piece Quick Disconnect Breakdown Whips		
	Whip 11.5x11.5 Mesh Flag	Whip 11.5x11.5 "X" Flag	Whip 16x16 "X" Flag	Whip 11.5x11.5 Mesh Flag	Whip 11.5x11.5 "X" Flag	Whip 16x16 "X" Flag
5ft	SW05QD-M	SW05QD-SXY	SW05QD-X	SW05QD2-M	SW05QD2-SXY	SW05QD2-XY
8ft	SW08QD-M	SW08QD-SXY	SW08QD-X	SW08QD2-M	SW08QD2-SXY	SW08QD2-XY
10ft	SW10QD-M	SW10QD-SXY	SW10QD-X	SW10QD2-M	SW10QD2-SXY	SW10QD2-XY
12ft	SW12QD-M	SW12QD-SXY	SW12QD-X	SW12QD2-M	SW12QD2-SXY	SW12QD2-XY



SW05QD-XY with AL8CA




SW08QD2-XY Breakdown whip shown above with optional LED whip light




Whip Extensions Fiberglass QD Mount Powered Custom lengths available

Size	Part Numbers
1 ft	EXT-1QD
2 ft	EXT-2QD
3 ft	EXT-3QD
4 ft	EXT-4QD
6 ft	EXT-6QD


Standard Flags



FLAG11-O:
11.5 x 11.5 inch
Orange (PMS 171 C)
Mesh flag








FLAG11-O-XY:
11.5 x 11.5 inch
Yellow (PMS Yellow C)
Mesh flag with reflective yellow X



FLAG16-O-XY:
16x16 inch
Orange (PMS 171 C)
Mesh flag with reflective yellow X

For other flag options, refer to page 20 Custom sizes available upon request.

Common LED Whip Lights

Product Number					
Flashing	AL8FR	AL8FA	AL8FB	AL8FW	AL8FG
Constant	AL8CR	AL8CA	AL8CB	AL8CW	AL8CG

other flight options available refer to page 21

Whip Mounts

Powered, for Quick Disconnect Mount

Steel QD Mounts



Stainless Steel QD Mount For quick disconnect whips,
a : SWQD-PT: wire in pigtail
b: SWQD-R: RCA Type power connector w/ RCA type pigtail,

Heavy Duty Spring Mounts



Heavy Duty Spring Mount Highly recommended to help reduce whip breakage.
c : 519.309 Stainless Steel
d : 519.30B Zinc Plated Steel

Angle Bracket Mounts (ABM)



ABM: Angle Bracket Mount Attach whips to toolbox, rack or truck bed with this heavy duty bracket.

Hitch Mount



HMQDA : Hitch Mount with Quick-Connect Mount and 107 dB Backup Alarm

For other mount options see to pages 16 to 19

Super Duty Whips

Added Locked-in Shielding seals components top and bottom.
See yellow Heat Shrink seals in detail photos at right

- 3ft to 12ft heights
- Threaded Base
- Powered
- Optional Flags
- Optional HD Spring

Part# SD05-X-30B-2CA as shown right
(5ft, 16"x16" X Flag, SD Zinc Plated Spring, AL2CA Amber LED Light)



Super Duty Whip Head



Super Duty Whip Base
Optional Super Duty Spring

Super Duty Fiberglass Whips

Product Number Chart

Super Duty (threaded base only)

Height (total)

- 03 (3ft)
- 05 (5ft)
- 08 (8ft)
- 10 (10ft)
- 12 (12ft)

Flag Type

- X (16x16 Reflective X)
- M (16x16 Mesh)

Example shown, SD05-X-30B-2CA
(Super Duty 5', Reflective X Flag, SD Spring Zinc Plated, AL2CA Amber LED)

LED Light Color

- R, B, G, W, A, RA
- LED Light Head Type
- Leave blank for none
- 2C (AL2C)
- 6F (AL6F)
- 8F (AL8F)

Super Duty Spring Mount

- Powered with 12" Fly Lead
- Leave blank for none
- 30B (SD Spring, Zinc Plated)
- 309 (SD Spring, Stainless Steel)

Heavy Duty LED Whips

SafetyWhips new Heavy Duty LED Whip increases light duty vehicle visibility.

*Other flags are available

Light Duty LED Whips

SafetyWhips new Light Duty LED Whip increases vehicle visibility.



New Item!

WL04A-XY



WL04R-XY



WL04G-XY



WL04B-XY



WL04W-XY

- Available in: Amber, Blue, Green, White and Red Colors
- Mine-Tough
- Rugged Polycarbonate Protection
- 12v or 24v Surge Protected
- Spring Mounted option for 4 to 8 ft whips (With spring option easily bends to 90° angle for storage)

Part Numbers	Length
WL04X-XY	4ft
WL06X-XY	6ft
WL08X-XY	8ft
WL10X-XY	10ft

X in part number is for LED Color: A, R, G, B or W

- Available in: Amber, Blue, Green, White and Red Colors
- Mine-Tough
- Rugged Polycarbonate Protection
- 12v or 24v Surge Protected
- Spring Mounted option for 4 to 8 ft whips (With spring option easily bends to 90° angle for storage)

Part Numbers	Length
WL04LX-SXY	4ft
WL06LX-SXY	6ft

X in part number is for LED Color: A, R, G, B or W



WL04LW-SXY
(Shown with Reflective Flag 11-0-SXY)



Sizes Available

- 1 FT EXT - 1
- 2 FT EXT - 2
- 3 FT EXT - 3
- 4 FT EXT - 4
- 6 FT EXT - 6

Optional Fiberglass Whip Extensions to extend to 8'-12'

Metal Whips Powered



- Extremely durable ATV Whips
- Up to 7ft
 - 1/4 inch Solid Steel Rod
 - Provides extra flexibility
 - 1156 type Light Socket
 - Black or Red Rod Sheathing
 - Deutsch Connector, Threaded Base
 - Also available in non-powered version

AW07D-X W/AL2CG: (at left)
 Red Rod Sheathing, optional Green light head,
 optional FLAG-16-X



Red Sheathing cut away to show rod


Light Duty Whips with Window Mount



Light Duty Window Mount, with Pole & Flag
 (non-powered only)

LWW05-M: 5ft Light Duty Whip
 w / Light Duty Window Mount and Mesh Flag

Light Duty Whips



Light Duty Whip:
 Available in white or red,
 1/4, 5/16, or 3/8 inch rod and up to 7 feet
 shown w/ 11x11 mesh flag

White
 ATV250: 1/4 inch rod
 ATV308: 5/16 inch rod (far left photo)
 ATV375: 3/8 inch rod

Red
 ATV250-R: 1/4 inch rod
 ATV308-R: 5/16 inch rod (near left photo)
 ATV375-R: 3/8 inch rod

Light Duty Whips with Magnet Mount



Magnet Mount with
 Light Duty Pole & Flag
 non-powered

LWM-BH-100 Magnet cup assembly
 OD 4.90" (Pull strength 220lbs)

LWM05-M: 5ft Light Duty Whip
 w / Magnet Mount and Mesh Flag
 LWM07-M : 7ft Light Duty Whip
 w / Magnet Mount and Mesh Flag
 (page 20 for other flags)

Telescoping Whips, Non-Powered

11 to 21 foot extending lengths



Part Number	Extended	Collapsed
TW11NP-X:	11 foot	79 inches
TW13NP-X:	13 foot	86 inches
TW15NP-X:	15 foot	93 inches
TW21NP-X:	21 foot	110 inches

Telescoping Whips: Whip is constructed of rigid wrapped fiberglass that is safe and non-conductive.
Heavy Duty Fiberglass, Non-powered with 3 Locking Sections, Reflective X (16 x16") Flag. *shown at left*



HMTNPA: Hitch Mount for Telescoping Whip w/ Back-up Alarm For Non-powered Whip



TW FMT: Telescopic Whip Flat Mount, w/ whip, locking pin. Non-powered mount, 10" x 10" flat plate with TW sleeve welded center, Powder Coated Black. Designed for applications when a hitch mount is not available.



4 mounting bolt holes 5/16, 1/4 inch Steel Plate, and weighs 7.8 lbs .

Side Extended Hitch Mounts and Back-up Alarm versions are on page 16

Telescoping Whips, Powered

11 to 21 foot extending lengths



Part Number	Extended	Collapsed
TW11D-X:	11 foot	79 inches
TW13D-X:	13 foot	86 inches
TW15D-X:	15 foot	93 inches
TW21D-X:	21 foot	110 inches

Telescoping Whips: Whip is constructed of rigid wrapped fiberglass that is safe and non-conductive.
Heavy Duty Fiberglass, Powered with 3 Locking Sections, Reflective X (16 x16") Flag. *shown at left*

(at right, shown in down position)
Telescoping Whips mounted in our HMTD: Hitch Mount for Telescoping Whip
Also shown at lower right



TW FMT: Telescopic Whip Flat Mount, w/ whip, locking pin. Non-powered mount, provides access to Tele-whip's RCA power input. 10" x 10" flat plate with TW sleeve welded center, Powder Coated Black. Designed for applications when a hitch mount is not available.



4 mounting bolt holes 5/16, 1/4 inch Steel Plate, and weighs 7.8 lbs .

Side Extended Hitch Mounts and Back-up Alarm versions are on page 16



HMTDA: hitch mount for Telescoping Whip with 7-Way power plug, Deutsch connector and Back-Up Alarm

Hitch Mounts, powered

Non-Powered Hitch mounts are available



Hitch Mounts are available with either a screw mount for the standard threaded whip, a quick release mount for quick connect whips or a telescoping adapter for telescoping whips and Breakdown Whips. **Specify 2 inch or 1.25 inch receiver.** Order with or without a 107 dB backup alarm.



hitch pin, optional part



HM1: Hitch Mount with Standard Screw Mount



HMQD: Hitch Mount with Quick-Connect Mount



HMTD: Hitch mount for Telescoping Whip with 7-Way power plug and Deutsch connector.



HM1S: Hitch Mount with Standard Screw Spring Mount
**107 db Backup Alarm available*



HM1A: Hitch Mount with Standard Screw Mount and 107 dB Backup Alarm



HMQDA: Hitch Mount with Quick-Connect Mount and 107 dB Backup Alarm



HMTDA: Hitch mount for Telescoping Whip with 7-Way power plug, Deutsch connector and Back-Up Alarm

Extended Hitch Mounts, powered

Non-Powered Hitch mounts are available

Extended Hitch Mounts allow you to use your vehicle's hitch receiver for warning whips while still being able to utilize your tailgate or rear hatch when necessary. Extended hitch mounts are available for solid fiberglass warning whips and for Telescoping Whips. **Mount only available for 2" or larger hitch receivers.**



HML1: hitch mount for threaded whip with 7-Way power plug



HML1A: hitch mount for threaded whip with 7-Way power plug and Back-Up Alarm



HMLQD: hitch mount for Quick Disconnect whip with 7-Way power plug



HMLQDA: hitch mount for Quick Disconnect whip with 7-Way power plug and Back-Up Alarm



HMLTD: Hitch mount for Telescoping Whip with 7-Way power plug and Deutsch connector.



HMLTDA: Hitch mount for Telescoping Whip with 7-Way power plug, Deutsch connector and Back-Up Alarm

Whip Mount Bases

Threaded Whip Receiving Mounts



- Steel Thread Mounts**
- a : 519.343NP Non-powered
 - b : 519.343.RCA RCA Type power connector w/ RCA type pigtail
 - c : 519.343 wire in pigtail

Quick Disconnect Receiving Mounts



- Stainless Steel QD Mount**
Use with quick disconnect whips
- d : SWQDNP: Non-powered
 - e : SWQD-PT: wire in pigtail
 - f : SWQD-R: RCA Type power connector w/ RCA type pigtail



Heavy Duty Spring Mount
Highly recommended to help reduce whip breakage.

*Shown with:
ABM: Angle Bracket Mount
See page 18*

Powered:

- g : 519.309 Stainless Steel
- h : 519.30B Zinc Plated Steel



Non-powder

- i : 519.309NP Stainless Steel
- j : 519.30BNP Zinc Plated Steel



Whip Mount Thread to QD Adapters

Thread to Quick Disconnect Adapters:
For use converting 1/2 inch 20 thread whip connection to QD
Available as Adapter Only or in Kit with Receiving QD Mount

Non-powered



- k : SWQD-KIT-NP, (kit)
- l : SWQD-WA-NP (adapter only)

Powered w/ lead



- m : SWQD-KIT-PT (kit)
- n : SWQD-WA (adapter only)

Powered w/detachable RCA lead



- o : SWQD-KIT-R (kit),
- p : SWQD-WA (adapter only)

Permanent Whip Mounts



519.821:
cigarette cord power adapter ships w/ Powered Magnet Mounts. Available as a separate part.



FDSM in Up position



Down position

FDSM: Fold Down Mount

Attaches whips to the truck side wall, tool box or back rack. It provides a quick and efficient way to fold whips down when leaving a job site or passing under low overhangs.



ABM: Angle Bracket Mount
Attach whips to toolbox, rack or truck bed with this heavy duty bracket.



FSM: Universal Flat Surface Mount

New Item!



FDVM Side Wall Mount

NEW – Side Wall Mount
Great for panel trucks and vans. Allows whip fold down to right or left
Whips up to 12 Ft
Use with RH01 Whip Retaining Hook (on page 24)

Temporary Whip Mounts



w/Quick-Disconnect

Medium Duty Magnet Mount
519.33LHR (red) Magnet mount, powered
A Quick-Release Mount is a typical option when ordering a Powered Magnet Mount.
Whips up to 8 Ft



519.33LRNP non powered



519.33LHRNP non powered



519.33LHR powered



519.33LR powered



Heavy Duty Magnet Mount 519.330

Shown with optional cigarette cord power adapter.
Whips up to 12 Ft



SPM: Stake Pocket Mount
Attach whip to this mount after slipping it into a truck's post hole and expanding the base.

Shown at left, Heavy Duty Aluminum, no drilling needed, a solid fit with adjustable base plates.



SW: Plate Mount

Steel Plate Mount for Non-Magnetic Applications

Allows use of magnetic warning lights, whips and other magnetic devices. Heavy Duty, flush-mounted plate with solid adhesive ensuring maximum security (easy to install).



519.320-V: Window Mount
Shown with optional cigarette cord power adapter.
Whips up to 8 Ft

Universal Platform Mount Systems

Ideal for Ford aluminum body trucks (non-magnetic) & all trucks as an alternative mounting location



Magnetic Based Strobe & Whip

Universal Platform Mount
Powder coated steel surface holds magnetic strobes and mounting holes allow devices to be bolted directly to the platform.



3 Sided Display & Whip bolted onto powder coated Universal Platform



UPMT : Toolbox/Side Wall Mount for Vertical Pole



- Use for VID Display (bolt on) & flag
- Magnetic based strobe & flag.
- Other accessories
- Side Wall or Hitch Mount Options



Hitch Mount options



For Hitch Mounting:
Order the hitch mount receiver separately, HMTD, HMTDA, HMLTD (extended) or HMLTDA (extended) as needed.




- | | |
|-----------|-------------------------------------------------------------------------|
| UPM5 | 5' Pole with Powered Triangle Platform |
| UPM5-TM | 5' Pole/ Platform with Thread Whip Mount |
| UPM5-S | 5' Pole/Platform with Thread Whip Mount and strobe |
| UPM5-V | 5' Pole/Platform with Thread Whip Mount and 3-sided Display |
| UPM5-VS | 5' Pole/Platform with Thread Whip Mount, strobe and 3-sided Display |
| UPM5-QD | 5' Pole/Platform with QD Whip Mount |
| UPM5-QDS | 5' Pole/Platform with QD Whip Mount and strobe |
| UPM5-QDV | 5' Pole/Platform with QD Whip Mount and 3-sided display |
| UPM5-QDVS | 5' Pole/Platform with QD Whip Mount and 3-sided display and strobe |
| UPM3 | 3' Pole with Powered Platform |
| UPM3-TM | 3' Pole/ Platform with Thread Whip Mount |
| UPM3-S | 3' Pole/Platform with Thread Whip Mount and strobe |
| UPM3-V | 3' Pole/Platform with Thread Whip Mount and 3-sided Display |
| UPM3-VS | 3' Pole/Platform with Thread Whip Mount and 3-sided Display with strobe |
| UPM3-QD | 3' Pole/Platform with QD Whip Mount |
| UPM3-QDS | 3' Pole/Platform with QD Whip Mount and Strobe |
| UPM3-QDV | 3' Pole/Platform with QD Whip Mount and 3-sided display |
| UPM3-QDVS | 3' Pole/Platform with QD Whip Mount and 3-sided display with strobe |
| UPMT | Side Mount for Telescoping Whips and Platform Mounts |

Flags

Mesh Pennant Safety Flag / Including Hog Rings

UV Resistant, Anti-Microbial and Fray Resistant

12w x 9h inch flags




FLAG-PO:
Orange

FLAG-PFY:
Fluorescent Yellow

Flag-PO-SY:
Orange
Yellow 3M Stripe

Custom Flags Available

Standard Flag Colors:



Other Colors Available

*PMS Colors - based on Pantone Matching System®

Mesh Safety Flag with Reflective X / Including Hog Rings x2

UV Resistant, Anti-Microbial and Fray Resistant

16w x 16h inch flags



FLAG16-O-XY:
Orange
reflective X
in yellow

FLAG16-Y-XW:
Fluorescent Yellow
reflective X
in white

FLAG16-O-XW:
Orange
reflective X
in white



Reflective Whip Sleeve
FLAG-RS24 : 24 inch length
FLAG-RS36 : 36 inch length
FLAG-RS59 : 59 inch length

Mesh Safety Flag with Reflective X / Including Hog Rings x2

UV Resistant, Anti-Microbial and Fray Resistant

11.5w x 11.5h inch flags



FLAG11-O-XY:
Orange
reflective X
in white

FLAG11-O:
Orange
reflective X
in yellow

FLAG11-M:
Orange



Metal "Flags":
Rigid, location flags can be
decaled as needed.
Shown on whip at left



Windsock and Hardware
Flag-WS18-96: Flag, 18x96, other lengths available



Flag-WS18-HW: (Hardware)



Light Duty Windsock
FLAG-WS8-19: Flag,

Airport Checkered Flag
Flag-APF: 36"x36"
Heavy-duty Nylon Airport Flag




LED Whip Lights

Mine Specification

24 Volt LED lights are available.

AL6FX: 6 LED Light Tubes 12V Animated

DAY / NIGHT VISIBILITY




- AL6FX:**
Added Features
- Strobing LED Light
 - Visible Night or Day and from Miles Away
 - 192 lumens brightness
 - Cross-QuadFlash
 - Fits 1156 (BA) Sockets

BRIGHTEST AVAILABLE WHIP LIGHT
192 lumens

White: AL6FW, Green-White: AL6FGW, Green: AL6FG, Amber-Green: AL6FAG, Amber: AL6FA, Amber-White: AL6FAW, Red-White-Blue: AL6FRWB, Blue: AL6FB, Blue-White: AL6FBW, Amber-Red: AL6FAR, Red-White: AL6FRW, Red: AL6FR

AL8FX: 8 LED Light Tubes 12V Animated

AL8CX: 8 LED Light Tubes 12V Non-Flashing



- Preprogrammed with 7 flash patterns for high visibility
- Durable and weather resistant
- LEDs rated to 100,000 hours
- Fits 1156 (BA) Sockets

Red: AL8FR, Blue: AL8FB, White: AL8FW, Green: AL8FG, USA: AL8FR-W-B-R, Multi-color R,G,B,A: AL8FMULTI



Red: AL8CR non-flashing



Amber, Red: AL8CAR non-flashing



Amber: AL8CA non-flashing

AL2CX: 2 LED Light Tubes 12V Non-Flashing **Low Profile**

Low Profile Super Bright 12V **4x Brighter than Standard 8LED lights!**

These Super Brights stay warm enough to melt snow and ice.



AL2CR Red non-flashing

AL2CG Green non-flashing

AL2CB Blue non-flashing

AL2CA Amber non-flashing

AL2CW White non-flashing

AL2CAR Amber, Red non-flashing

- This tough light is completely filled with optically clear gel for added robustness.
- 2-LEDs, Non-Flashing
- 100,000 Hours
- Extra bright
- Available in 5 colors and Red/Amber
- Fits 1156 (BA) Sockets

AL4CX: 4 LED Light Tubes 12V Non-Flashing



- 360 degree, Bi-directional
- Available in amber, (left) also red, white, blue & green
- Fits 1156 (BA) Sockets

AL16FX: 16 LED Light Tubes 24V Animated



- Advanced Circuitry
- 24 Volt Input
- 16 LED, 8 per side
- Fits 1156 (BA) Sockets
- Weather resistant in Polycarbonate Tubing
- Available in red, (shown at left) also, amber, green & white
- "X" = A,R,W,G Color

24V

LED Whip Lights

LED Whip Light Part Number Matrix

Product Number

example

AL8

F

R

Light Type

AL8: Standard Night Visibility
Flashing (F) or Constant (C)

AL6: Low Profile, Super Bright
Flashing only (F)

AL2: Low Profile, Super Bright
Constant (C), Non-flashing only

Flash or Constant

F: Flashing
C: Constant

LED Colors

- A: Amber
- B: Blue
- G: Green
- R: Red
- W: White
- AR: Amber/Red
- USA: Red/White/Blue*
- MULTI: Red/Green/Blue/Amber**

* USA not available in AL2 type
 ** Multi not available in AL2 or AL6 types

Custom options available

Battery Powered Options



9 VOLT BATPACK: Use for a great temporary alternative to hard-wiring your whip. An excellent back-up power supply for your AL8F or AL6F whip-top lights
 Expected hour of use:
 With AL8F-CLED, 25 to 30 hours
 With AL6F LED, 12 to 15 hours



BATPACK-ER KIT: The BatPack-ER Kit, fits an existing 1156 socket whip or use set-screw base. It can also be used as a temporary light source in lieu of wiring. Includes both base options, the 3 CR2 3 V batteries, and AL8F light (in your choice of color).



Lamp Shields

Lamp Shields: High impact plastic to protect Automotive Type Bulbs on whips and changes color.

Lamp Shields, full cover: High impact plastic to protect Automotive Type Bulbs on whips and changes color.

ML-PLR



ML-PLG



ML-PLA



Lamp Shields Covers



12 Volt 2.1 Amp SC Bayonet Bulb



ML-TA,



ML-TR



Warning Lights



SW-255TS-"color"



Available in:
Red, Amber, Clear, Blue and Green lenses

The SW255TC and SW255TS Series offer field selectable flash patterns of double flash or quad flash via an internal jumper. The polycarbonate lens easily twists on/off the durable and lightweight polycarbonate plastic, universal mount, flanged base. The circuit is completely encapsulated for increased shock and weather resistance and is also protected with a low voltage shutdown feature. Ships complete with mounting hardware and instructions.



SW-255TSM-"color"



SW255TC Series:
SW255TC: Flange Mount
SW255TCM: Magnetic Mount
SW255TCV: Vacuum Magnetic Mount
High Dome: 6-11/16"H x 6-13/32"Dia., 3 lbs.

SW255TS Series:
SW255TS: Flange Mount
SW255TSM: Magnetic Mount
SW255TSV: Vacuum Magnetic Mount
Low Dome: 4-3/4"H x 6-13/32"Dia., 3 lbs.



SW-255TSV-"color"



SW255TC & SW255TS Specifications:
Mounting: Universal Flange Mount
1" Pipe mount Magnetic Mount
Vacuum Magnetic Mount
Approvals: SAE J1318 Class 2:
Amber, Blue, Clear, Red (Quad Flash only)

Voltage: 12V-48V DC
Amp Draw: 1.2 Amps @ 12V DC
0.6 Amps @ 24V DC
0.3 Amps @ 36V DC
0.175 Amps @ 48V DC:
Double Flash: 7 joules
Quad Flash: 10 joules
Lens color: Amber, Blue, Clear, Green, Red



SW9200S-X,
SW9200SM-X
SW9200SV-X

*Many Warning Light
options and models available.*

Emergency Light Bars

SW9100LED-A



10-30 VDC
L 16 1/2", W 8 3/8", H 2"

SW9100LED-Clear



10-30 VDC
L 16 1/2", W 8 3/8", H 2"

SWDLX6-AA



10-30 VDC
L 3 5/8", W 1 15/16", H 1"
bracket mount only

SWDLX4-Clear



10-30 VDC
L 3 5/8", W 3/4", H 1"

SW2440



2400LED:
L 46", W 15", H 2 3/4"
10-16VDC

SW2464LED-A



2464LED:
L 46", W 15", H 2 3/4"
10-16VDC

SW7400




7400LED:
L 46", W 12 1/4", H 2 5/8"
10-16VDC

SW7464LED



7464LED:
L 46", W 12 1/4", H 2 5/8"
10-16VDC

Accessories



a: RCA.1: Dual-wire, Right angle Plug
b: RCA.2: Dual-wire, Straight Plug
c: HP.2: Single-wire, Hot Plug



RCA.D :
Deutsch DT Series 2 pin connector.
This Dual-wire connector offers extra protection in harsh environments



HM-TRAILER PLUG:
Pollak 7-Way Trailer End Plug



d: TWMD
e: TWFD
Deutsch DT Series 2 pin connector.
RCA to Deutsch Adapters



HM-B/U-alarm 107db
Backup Alarm, 107db
This compact, high sound level alarm is specifically designed for 107 decibels. This solid state alarm is polarity protected. The 270 alarm has an approximate current draw of 0.5 Amps. Self-resonating circuitry automatically adjusts to environmental conditions to ensure a constant 107 decibel output. Weight: 12 oz. (340 g)



519-DC/DC converter:
24 to 12 Volt DC Converter



519.821: cigarette cord 10 ft.,
power adapter



RH01 Hold-down Hook
Hold-down hook for Fiberglass Whips



First Aid and Body Fluid Clean-up Kits



First Aid Kit for 10 persons
Plastic Adhesive Strips, Bandages, Gauze Pads, Gauze Bandage, Adhesive Tape, Antiseptic Towelettes, Aid/Burn Cream Packets, Bandage Scissors, Forceps, Gloves, First Aid Guide

FA-10P



Body Fluids Clean-up Kit

FA-BP



First Aid Kit for 25 persons
This industrial First Aid Kit is designed for a 25-person workplace meeting OSHA requirements but also ideal for any office or home. The compact metal case is easily transportable with convenient handle and easily stowable or wall-mountable. Cold-pack, Plastic Adhesive Strips, Bandages, Gauze Pads, Gauze Bandage, Adhesive Tape, Antiseptic Towelettes, Aid/Burn Cream Packets, Gloves, First Aid Guide, medical scissors and tweezers,

FA-25P

Aviation / Transportation Safety



Windsock and Hardware

Flag-WS18-96: Flag, 18x96 , other lengths available Flag-WS18-HW: (Hardware)

Airport Checkered Flag
Flag-APF: 36"x36"
Heavy-duty Nylon Airport Flag



Light Duty Windsock
FLAG-WS8-19: Flag,



WC-1100BY-R2 2 roped chocks	
4 L • 8 W • 4 H in	7.5 lb
10.16 L • 20.32 W • 10.16 H cm	3.40 kg



Snow plow whip



HD Fiberglass Whip with HD Spring. show at left. see specifications on page 12

Fire Hydrant Mount



FHM: Fire Hydrant Mount
Find Hydrant in deep snow and avoid over-plowing and drive overs

3M Scotchlit™ Diamond Grade™

This reflective prismatic sheeting offers optimum visibility for the backs and sides of trucks. This Prismatic effect produces a high visibility from multiple angles.

3M Conspicuity Tape, DOT marking for vehicles and signage.

- 7 year warranty not to fade, crack, peel or discolor.
- Meets NHTSA Regulations 49 CFR 571.108 and FHWA 49 CFR 393.13
- Reflects up to 900 candlepower brightness
- Precut alternating color sections for easy application
- Superior visibility from all angles

TAPE-2-RW: Adhesive, Red and White, also available in other colors

TAPE-2M-G: Magnetic, Green, also available in other colors

- Magnetic or adhesive
- Single or Multi-Color
- 50' or 150' rolls
- 1 to 4 inch width



Road Hazard Kit



Features: 3-Safety triangles with bases
Fluorescent strips provide maximum warning day or night
Reflectors sealed from dust & moisture,
Plastic-hinged storage case.
4- Road Flares, Road Flares
20 min RED, no stand, no spike

Aviation / Transportation Safety



SAFETY FLAGS ON DOWEL: Mesh Safety Flag Heavy Duty
These Mesh Flags are made of fluorescent knitted vinyl (KV) mesh material.
Recommended to be used on fast moving vehicles.
These flags will overcome the objections from "whipping," such as cracking, peeling, or fraying.

To Order Specify :
Flag Type: Heavy Duty Mesh or Vinyl
Flag Size: 18"x18" or 24"x24"
Dowel Length: 18", 24", 36" or 48"

Fire Extinguishers




Fire Extinguishers Available in 5 lbs, 10 lbs, 20 lbs and 30 lbs, vehicle brackets available
Buckeye's Monoammonium Phosphate fire extinguishers are designed for use in combating Class "A", "B", and "C" type fires. ABC extinguisher provides the widest and most practical range of extinguisher protection coverage. ANSI/UL 299 and ANSI/UL 711 standards. US Coast Guard approved for Type B:C



Fire Extinguishers Brackets
FE-VB-10t-HD for 10 lb Tall dry chemical, 5.0 in. – 5.25 in.f
FE-VB-20/30-HD for 20 lb and 30 lb dry chemical, 20 lb CO², Class D, 7.0 in. – 8.0 in.

Personal Safety



Hard Hats

Hard Hat - Full (A, in photo) Lightweight
Reduces impact of falling objects, but does not provide unlimited protection. 4-Point nylon suspension
Adjustable head strap w/ ratchet head strap.

Hard Hat - Front (B, in photo) Lightweight with.
Superior fit and comfort. Swivelling pivot head strap.
Adjustable pinlock or ratchet-style head strap.
4 or 6-point nylon suspension.

Add Your Logo to Hard Hats



Contact us for Logo, Safety Decals or Certification Stickers from Industrial Decals Co.

Safety Vest



SSVM-GR-"size" no photo available
Mesh panels in upper front and mid-back
Multi-pocket Surveyors Vest, zipper
Green, Med, Large, XL, XXL, XXXL

SSV-GN-"size": shown above
Multi-pocket Surveyors Vest, zipper
Green, Med, Large, XL, XXL, XXXL



SSV-OR-"size" shown above
Multi-pocket Surveyors Vest, zipper
Orange, Med, Large, XL, XXL, XXXL



SSVM-OR-"size" shown above
Mesh panels in upper front and mid-back
Multi-pocket Surveyors Vest, zipper
Orange, Med, Large, XL, XXL, XXXL



SV014: Vest, Fluorescent Soft Mesh with Reflective Yellow

shown with
AB011: Arm Band Fluorescent Reflective



SV012: Fluorescent yellow mesh with zipper



SafetyWhips USA 2115 W. Mountain View Rd., Phoenix, AZ 85021
 Tel. 602-424-2500 Fax: 602-424-9777
 Sales@SafetyWhips.com
 www.SafetyWhips.com

SW SafetyWhips Canada, 677 – 192 St. #107 Surrey, BC V3S 3X1
 tel 604.560.5080 fax 604.560.5090
 Lugo@safetywhips.com
 www.SafetyWhips.ca



Vehicle Wraps, Graphics & Lettering
 OSHA / MSHA / ANSI Compliant :
 Decals, Signs, and Tags

Contact Industrial Decals Co. at – tel 602.235.0085
 Email: Sales@Industrialdecalsco.com

www.Industrialdecalsco.com



Equipment ID Decals

Item Branding



Vehicle Wraps



DOT Placards and Signs



Custom NFPA Diamond Signs




Customize Any Decal



Bar Coding

Chemical Hazmat



Fire Extinguisher Tags

OSHA Safety Signs and Decals



- Branding for Vendors & Distributors
- Product & Marketing Labeling
- Control Panels
- Hard Hat Decals
- Magnetic Signs
- Vehicle Wraps, Graphics & Lettering
- Window Graphics
- Banners
- Wall Murals
- Pull-up Graphics